Replies to Bidder Queries - Estimate for Providing And Laying 1000/1200/1800/2000mm Dia RCC NP-3 Class Sewer Line from 7th Main Garvebhavipalya along HSR Layout upto agaram STP and construction of ISPS at HSR Layout under AEE(WWM-N) K&T Sub Division at Various Location.

Sl.No	Reference		Ammendment requested	Reply
	Tender Clause	Description		
1	Clause No.3.2c(b) on Page No.9	Construction of ISPS of 12 MLD Capacity	We request you to please consider the work done of Jackwell and Intake Well as the nature of work is similar type.	Tender conditions prevails
2	In BOQ: Item No. 34, 35,36, 37& 38	For manufacture of RCC NP3 Pipe by using Ordinary Portland Cement(OPC)	**Please clarify** :- Chapter 10 of Section-7 It. No 10.1 in Page No.107, it is mentioned that Sulphate Resistant Cement (SRC) and **in Previous tenders it is mentioned RCC NP 3 pipes are marked with ISI**. The same has not been considered. Please consider the same.	Tender conditions prevails and RCC NP-3 pipes should be marked with ISI.
3	Engineer's Requirement on Page No.22 of PART-3	Requiremet of Site Office including Furnitures, Survey Instruments & Personal Computer and LapTop with accessories, Printers	The same has not been considered in BOQ. The cost for the same is to be considered, during the tender evaluation or delete from the contract.	Tender conditions prevails
4	Engineer's Requirement on Page No.22 of PART-3 Specification - Transport	The Contractor shall provide two New Top end Maruthi Suzuki Grand Vitara hybrid version fully loaded to be kept available at all times for the sole use of the Engineer and his staff.	For providing vehicle, we would like to inform you that, recently in Arkavathi Wss Tender, the same was included by incorporating to provide vehicle and the capital cost of vehicle will be reimbursed at actual cost under provisional sum excluding insurance.The same has not been considered. .Either you may consider the same or delete from the contract.	The contractor shall provide one new top end INNOVA CRYSTA to be kept avilable at all times for the sole use of Engineer and his staff.
5	Volume II: Part 3 General Requirements: Engineer's Requirements: Vehicle	The Contractor shall purchase and maintain one new INNOVA top/ highend/ Equivalent vehicle for the contract to be kept available at all times for the sole use of the Engineer and his staff at contractor's cost	For providing vehicle, we would like to inform you that, recently in Arkavathi Wss Tender, the same was included by incorporating to provide vehicle and the capital cost of vehicle will be reimbursed at actual cost under provisional sum excluding insuracne.The same has not been considered.Either you may consider the same or delete from the contract.	The contractor shall provide one new top end INNOVA CRYSTA to be kept avilable at all times for the sole use of Engineer and his staff.
6	Chapter 2 of Section-7 It. no 4.26 c in page no. 49	Royalty recovery for hard rock not mentioned in Tender document	Please clarify	Rs. 70 per Cum plus applicable GST of Hard rock will be recovered from running bills for the qty of payment made.
7	Chapter 4 Vol:2 page no. 50	Rock excavation	Charges and recovery in running bills for Rock excavtion recently in MV Garden Tender its stated that The Hard Rock obtained during execution, will not be auctioned by Board (Because of the restriction in stacking of hard rock in site and safety issues). However **Rs.70.00 per cum + applicable GST** of Hard Rock will be recovered from the firm Running bills.The same has not been considered. Please consider the same.	Considered
8	Part 2 Vol: 2 Page No. 18	Once the Engineer's approval has been given the Contractor shall be solely responsible for maintenance of the existing site access roads. This responsibility shall continue until the completion of the Defects Liability Period, or until such earlier date as the Engineer may advise the Contractor in writing. Such maintenance work shall include general up-keeping and any necessary repairs to damaged road surfaces, pavement, drainage	The same has not been considered in BOQ. The cost for the same is to be considered during the tender evaluation. Please clarify.	Tender conditions prevails
9	Part 2 Vol: 2 Page No. 18	**Permission from Service Agencies:** The Contractor, who is the sole responsible to get the necessary permission from service agencies, such as, BBMP, BDA, Traffic Police, KPTCL, etc. the delay in getting the permission will not be taken into account. The contractor shall obtain the Engineer's permission for carrying out the works such as, excavation on the existing roads, Employer will assist contractor to issue the letter to the concerned department, if necessary.	In previous tenders **All required permissions/ ROW issues from all concerned departments such as NHAI / Railways / any other department shall be obtained from the contractor and Board Engineers will assist for the same. Deposits payable to the departments will be borne by the Board.** Please consider the same	Board Engineers will assist for obtaining the permission/NOC from the concerned departments and any Deposits payable to the departments shall be borne by the contractor and the same will be reimbursed on actual basis by submitting the necessary bill.
10	Part 2 Vol:2 Page No. 31	**Payments of items on lump sum basis:** For which tender premium are applicable.	Please consider the bifurcation of payment for ISPS/ SUMP/ PUMP etc., brought out items.	Payment will be made as per the breakup of the estimate.
11	Part 2 Vol:2 Page No. 32	Maintenance of underground utility services	Any utility damaged during excavation will be restored by contractor, but due to alignment, if any utilities shifting to be made, the expenses should be borne by board. Please consider.	Tender conditions prevails
12	Volume 1 page no 5 in table Performance and work Qualification	b) As a Prime Contractor, the tenderer should have satisfactorily completed at least one similar work of value not less than Rs.4794.59 . In case of JV in this contract lead partner shall meet minimum 50% of required turnover and 2 partner shall meet minimum 25% of require turnover.		Shall be read as b) As a Prime Contractor, the tenderer should have satisfactorily completed at least one similar work of value not less than Rs.4794.59 Lakhs In case of JV in this contract lead partner shall meet minimum 50% of required turnover and 2 partner shall meet minimum 25% of require turnover.

Sl.No	Reference		Ammendment requested	Reply
	Tender Clause	Description		
13	Part 2 Vol:2 Page No.95	Payments for **Steel Sheet Piling**	During the construction of ISPS special materials are used for Sheet piling. Please consider removal of 10% additional deduction for ISPS Works	Tender conditions prevails
14	Part 2 Vol:2 Page No.101	(xi) **Steel Fibre Reinforced Concrete (SFRC) Frame and Cover**	Please Specify the class of SFRC frame and covers used for Machine holes either **heavy or extra heavy duty** to be used.	Heavy duty SFRC frame and cover.
15	Part 2 Vol: 2 Page No.108	CHAPTER 10: **RCC SOCKET SPIGOT NON-PRESSURE PIPES**: (vi) The pipes shall be provided either with High Alumina Cement or Poly Urea internal lining to protect from corrosion, thus ensuring long life.	In BOQ there is no provision for Polyurea or high alumina lining for RCC NP3 pipes. In previous tenders in RCC NP3 Class Pipe manufacturing, there is no consideration of Polyurea lining or High Alumina Cement lining. Please Conisder the same	RCC NP-3 pipes without any Polyurea lining or High Alumina Cement lining.
	In BOQ			
16	Sl.No:6, 7, 8 and 9	Type of soil not mentioned	Please clarify	item no 6,7- Ordinary soft rock without requiring blasting.Item no8,9 -Hard rock without requiring blasting.
17	Sl.No:11 Item code:A00006	Grade of concrete not mentioned	Please clarify	Mix 1:3:6 using 20mm nominal size graded crushed aggregates
18	Sl.No:13 Item code:A00008	In the name of work and drawing, it is mentioned Pipe dia 1600mm, but in specification, it is mentioned as 1800mm	Please clarify	Shall be read as 1600mm dia
19	Sl.No:45 Item code:B00003b	Type of soil not mentioned in specification	Please clarify	Ordinary soft rock without requiring blasting
20	Sl.No:52 Item code:B00006	Grade of concrete not mentioned	Please clarify	Mix 1:3:6 using 20mm nominal size graded crushed aggregates
21	Sl.No:130,131 Item code:E00003a & 3b	Type of soil not mentioned in specification	Please clarify	Ordinary soft rock without requiring blasting
22	Sl.No:133 Item code:E00005	Grade of concrete not mentioned	Please clarify	Mix 1:3:6 using 20mm nominal size graded crushed aggregates
23	Sl.No:159 and 160 Item code:F00003a & 3b	Type of soil not mentioned in specification	Please clarify	Ordinary soft rock without requiring blasting
24	Sl.No:161 Item code:F00004	Sheet piling depth has not mentioned in specification	Please clarify	Depth -3.0m to 6.0m
25	Sl.No:178 Item code:F000015	Pipe diameter is not mentioned in specification	Please clarify	300mm Dia
26	Sl.No:184 Item code:F000021	Grade of steel is not mentioned	Please clarify	shall be read as TMT Fe550 grade.
27	-	-	We request you to please provide make for Electro-Mechanical items of work to consider in the tender.	Refer Vol 02 of part 11 .

Addl. Chief Engineer
(WWM-Network-East)
BWSSB

Chief Engineer (WWM)-East
BWSSB, Cauvery Bhavan,
K.G. Road, Bengaluru - 560 009